

Sl. No.	Description	Unit	Sanctioned			CSR 2015-16		Rates	Amount
			Qty	Rate	Amount	Rates	Amount		
54	SUPPLYING AND FIXING OF PENDULUM DOUBLE OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B- class Pipe, LEG FRAME : 40 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	900000.00	3600000.00	900000.00	3600000.00	1100000.0	4400000.00
55	SUPPLYING AND FIXING OF SHOULDER PRESS DOUBLE OF SAFE AREA : 4 MTR X 2.5 MTR OF CENTRE PIPE : 100 NB GI B-CLASS Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, NUT-BOLT CAP : Nylon 66 injection moulded, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	2.00	1800000.00	3600000.00	1800000.00	3600000.00	2000000.0	4000000.00
56	SUPPLYING AND FIXING OF CYCLE TWO WAY OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B-CLASS Pipe, ARM FRAME : 40 NB GI B-CLASS Pipe, HANDLE FRAME : 20 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	2.00	1050000.00	2100000.00	1050000.00	2100000.00	1200000.0	2400000.00
57	SUPPLYING AND FIXING OF TAI CHI SPINEER DOUBLE OF SAFE AREA : 2 MTR. DIA, MAIN FRAME : 100NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SPINNING RING : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	900000.00	2700000.00	900000.00	2700000.00	1000000.0	3000000.00
58	SUPPLYING AND FIXING OF TWISTER THREE WAY OF SAFE AREA : 2.5 MTR. DIA, MAIN FRAME : 100 NB GI B - class Pipe, ARM FRAME : 32 NB GI B - CLASS Pipe, HANDLE FRAME : 20 NB GI B - CLASS Pipe, TWISTER DISC : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	900000.00	2700000.00	900000.00	2700000.00	1000000.0	3000000.00
59	SUPPLYING AND FIXING OF CHEST PRESS DOUBLE - OF SAFE AREA : 4 MTR X 2.5 MTR, OF CENTRE PIPE : 100 NB GI B-CLASS Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	1800000.00	5400000.00	1800000.00	5400000.00	2100000.0	6300000.00
60	SUPPLYING AND FIXING OF FUN ROVER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B- class Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	4.00	620000.00	2480000.00	620000.00	2480000.00	700000.0	2800000.00
61	SUPPLYING AND FIXING OF FUN RIDER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B- class Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK.	No.	3.00	1500000.00	4500000.00	1500000.00	4500000.00	1750000.0	5250000.00

Sl. No.	Description	Unit	Sanctioned			CSR 2015-16		Rates	Amount
			Qty	Rate	Amount	Rates	Amount		
62	SUPPLYING AND FIXING OF STEP TRAINER OF SAFE AREA : 3 MTR X 1.5 MTR, MAIN FRAME : 100 NB GI B-class Pipe, BOTTOM FRAME : 40 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, FOOT REST : LLDPE Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER	No.	3.00	181500.00	544500.00	181500.00	544500.00	210000.0	630000.00
63	SUPPLYING AND FIXING OF ROLLING BARREL DOUBLE OF SAFE AREA : 2.8 MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDPE Plastic, SEAT REST : LLDPE Plastic, FOOT REST : LLDPE Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER IN	No.	3.00	144000.00	432000.00	144000.00	432000.00	165000.0	495000.00
64	Providing and erecting direction and place identification retro- reflectorised sign as per IRC :67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing complete as per specifications. NORTH Specification No.801 Using Type IV sheeting	Sqm	1.00	7509.24	7509.24	7509.24	7509.24	8500.0	8500.00
65	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum.	191.48	187.01	35808.67	187.01	35808.67	200.0	38296.00
66	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum.	40.00	5236.92	209476.80	5236.92	209476.80	6000.0	240000.00
67	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20	Cum.	71.48	6332.04	452614.22	6332.04	452614.22	7000.0	500360.00
68	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	24.00	306.72	7361.28	306.72	7361.28	350.0	8400.00
69	Vacuum de-watering with vacuum pump and suction mat and compaction with skip floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	400.00	97.20	38880.00	97.20	38880.00	110.0	44000.00
70	Providing groove cutting for width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillers, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.	Rmt	240.00	124.20	29808.00	124.20	29808.00	140.0	33600.00
71	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	No	1424.00	320.76	456762.24	320.76	456762.24	370.0	526880.00
72		Sqm	72.00	61.56	4432.32	61.56	4432.32	70.0	5040.00

Sl. No.	Description	Unit	Sanctioned				CSR 2015-16		Rates	Amount
			Qty	Rate	Amount		Rates	Amount		
73	Providing and constructing standard rubber flooring for Outdoor areas using rubber membrain of 12mm thick to be layed over Praepared Cement Morter/Concrete surface using CM1:6 Beneath rubber membrain including cost of all materials labour packing joints and mortor, finishing curing all Lead & lift transportation and also including all applicable taxes etc, cmplete as per direction of engineer incharges of work.	Sqm	400.00	5164.80	2065920.00		5164.80	2065920.00	6000.0	2400000.00
74	SUPPLYING AND FIXING OF LEG PRESS DOUBLE OF SAFE AREA : 2.8MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS PIPE, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER	No.	4.00	90000.00	360000.00		90000.00	360000.00	120000.0	480000.00
75	SUPPLYING AND FIXING OF FUN WALKER DOUBLE OF SAFE AEA : 3 MTR X 2 MTR, MAIN FRAME : 100 NB GI B-class Pipe, LEG FRAME : 32 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMENANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BPLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER	No.	6.00	150000.00	900000.00		150000.00	900000.00	175000.0	1050000.00
76	SUPPLYING AND FIXING OF PENDULUM DOUBLE OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B- class Pipe, LEG FRAME : 40 NB GI B- CLASS Pipe, HANDLE FRAME : 25 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE	No.	4.00	90000.00	360000.00		90000.00	360000.00	105000.0	420000.00
77	SUPPLYING AND FIXING OF SHOULDER PRESS DOUBLE OF SAFE AREA : 4 MTR X 2.5 MTR OF CENTRE PIPE : 100 NB GI B-class Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, NUT BOLT CAP : Nylon 66 injection moulded, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON	No.	4.00	180000.00	720000.00		180000.00	720000.00	200000.0	800000.00
78	SUPPLYING AND FIXING OF CYCLE TWO WAY OF SAFE AREA : 2.5 MTR X 1 MTR, MAIN FRAME : 100 NB GI B-class Pipe, ARM FRAME : 40 NB GI B-class Pipe, HANDLE FRAME : 20 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER	No.	4.00	105000.00	420000.00		105000.00	420000.00	120000.0	480000.00
79	SUPPLYING AND FIXING OF TAI CHI SPINER DOUBLE OF SAFE AREA : 2 MTR. DIA, MAIN FRAME : 100NB GI B-class Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SPINNING RING : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS	No.	5.00	90000.00	450000.00		90000.00	450000.00	105000.0	525000.00
80	SUPPLYING AND FIXING OF TWISTER THREE WAY OF SAFE AREA : 2.5 MTR. DIA, MAIN FRAME : 100 NB GI B - class Pipe, ARM FRAME : 32 NB GI B - CLASS Pipe, HANDLE FRAME : 20 NB GI B - CLASS Pipe, TWISTER DISC : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE	No.	4.00	90000.00	360000.00		90000.00	360000.00	105000.0	420000.00

Sl. No.	Description	Unit	Sanctioned			CSR 2015-16		Rates	Amount
			Qty	Rate	Amount	Rates	Amount		
81	SUPPLYING AND FIXING OF CHEST PRESS DOUBLE - OF SAFE AREA : 4 MTR X 2.5 MTR, OF CENTRE PIPE : 100 NB GI B-CLASS Pipe, SEAT FRAME : 32 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, SEAT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	No.	4.00	180000.00	720000.00	180000.00	720000.00	200000.0	800000.00
82	SUPPLYING AND FIXING OF FUN RIDER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B-CLASS Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	No.	4.00	62000.00	248000.00	62000.00	248000.00	70000.0	280000.00
83	SUPPLYING AND FIXING OF FUN RIDER, SAFE AREA : 2.5 MTR X 1.5 MTR., MAIN FRAME : 80 NB GI B-CLASS Pipe, SEAT FRAME : 80 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB GI B-CLASS Pipe, SEAT : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	No.	4.00	150000.00	600000.00	150000.00	600000.00	175000.0	700000.00
84	SUPPLYING AND FIXING OF STEP TRAINER OF SAFE AREA : 3 MTR X 1.5 MTR, MAIN FRAME : 100 NB GI B-CLASS Pipe, BOTTOM FRAME : 40 NB GI B-CLASS Pipe, HANDLE FRAME : 32 NB & 15 NB GI B-CLASS Pipe, Handle cover : TPEE injection moulded, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	No.	4.00	181500.00	726000.00	181500.00	726000.00	210000.0	840000.00
85	SUPPLYING AND FIXING OF ROLLING BARREL DOUBLE OF SAFE AREA : 2.8 MTR X 1.5 MTR, CENTRE PIPE : 100 NB GI B-CLASS, SEAT FRAME : 32 NB GI B-CLASS Pipe, BACK REST : LLDP Plastic, SEAT REST : LLDP Plastic, FOOT REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : Seamless Pipe & Round Bar, BEARING : PERMANENT SEALED OF REPUTED MAKE (FAG/SKF), STOPPER : PU ROD, NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70 - 80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	No.	4.00	144000.00	576000.00	144000.00	576000.00	165000.0	660000.00
86	Providing and erecting direction and place identification retro- reflectorised sign as per IRC : 67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801 Using Type IV sheeting	Sqm	2.00	7509.24	15018.48	7509.24	15018.48	8700.0	17400.00
Total					19004526.31		18906642.59		22051361.25
Tender Premium Percentage compared to Sanctioned Estimate rate of SR 2015-16									16.03%
Tender Premium Percentage compared to Current rate of SR 2015-16									16.63%


 Executive Engineer,
 Project Division, R.R. Nagara Zone.
 Bruhat Bangalore Mahanagara Palike.